



PP3015 & PP3015S Snow Guards Specification Sheet

Snow Guards

PART 1 – GENERAL

1.1 SUMMARY

A. WORK INCLUDES

1. PP3015 & PP3015S Snow guards that attaches directly to the roof deck.
2. Coordinate with the installation of the roof to assure proper placement of the snow guards.
3. Provide appropriate snow guard and fasteners for the roof system

B. RELATED SECTIONS

1. Section 07600: Flashing and Sheet Metal. MasterFormat™ 2004 07 60 00
2. Section 07500: Membrane Roofing. MasterFormat™ 2004 07 50 00
3. Division 1: Administrative and procedural requirements.
4. Division 7: Thermal and Moisture Protection

1.2 SYSTEM DESCRIPTION

A. COMPONENTS:

1. Both snow guard systems consists of snow guard bracket, attachment block (F-202) and base plate with (2) stainless steel nuts and (2) bonded stainless steel and EPDM washers.
2. PP3015
 - a. Tubing (Snow Fence).
 - b. Couplings.
 - c. End Caps.
 - d. End Collars.
 - e. Ice Flags
3. PP3015S
 - a. VersaClip
 - b. Aluminum (Snow Fence).
 - c. Color Strip (optional – can be provided by others).



4. Fasteners
 - a. To be of metal compatible with snow guards.
 - b. Fasteners should be selected for compatibility with the roof deck.
 - c. Fastener strength should exceed or be equal to that of the snow guard system.
5. Flashing Patch of appropriate size, material and method of installation to meet roof manufacturer's requirement for proper flashing.

B. DESIGN REQUIREMENTS:

1. Bracket spacing to be recommended by snow guard manufacturer or building engineer.
2. Install a minimum of 8 fasteners per snow guard base plate.
3. It is important to design new structures or assess existing structures to make sure that they can withstand retained snow loads.

1.3 SUBMITTAL

- A. Submit manufacturer's specifications, standard detail drawings, installation instructions, and recommended layout

1.4 QUALITY ASSURANCE

- A. Installer to be experienced in the installation of specified roofing material and snow guards for not less than 5 years in the area of the project.

1.5 DELIVERY / STORAGE / HANDLING

- A. Inspect material upon delivery and order replacements for any missing or defective items. Keep material dry, covered and off the ground until installed.

PART 2 – PRODUCTS

2.1 MANUFACTURER

- A. Alpine SnowGuards. A division of Vermont Slate & Copper Services Inc.,
289 Harrel St. Morrisville, VT 05661, (888) 766-4273
www.alpinesnowguards.com



2.2 MATERIALS

- A. Snow Guard Bracket - 6000 Series Aluminum.
- B. Base Plate - 11 gage 304 stainless steel with two 5/16" 304 stainless steel machine screws welded into countersinks.
- C. Attachment Block (F-202) – Series 6000 Aluminum.
- D. PP3015
 - 1. Tubing (choose one):
 - a. Aluminum – 6000 Series, 1" outside diameter and .120" wall thickness, extruded
 - b. Stainless Steel – 304 alloy, same dimensions as aluminum, welded.
 - 2. Couplings (choose one):
 - a. Aluminum – 6000 Series
 - 1. Internal and concealed coupling 3" long.
 - 2. External and exposed coupling which can also serve as an expansion mechanism 5" long.
 - b. Stainless Steel – 304 Series
 - 1. Internal and concealed coupling 3" long.
 - 2. External and exposed coupling which can also serve as an expansion mechanism 5" long.
 - 3. End Caps - 304 Stainless Steel.
 - 4. End Collars (choose one):
 - a. 6000 Series Aluminum.
 - b. 304 Stainless Steel.
 - 5. Ice Flags (choose one):
 - a. 6000 Series Aluminum 3" wide x length (as needed).
 - b. 304 Stainless Steel.
- E. PP3015S
 - 1. VersaClip – 6000 Series Aluminum.
 - 2. Aluminum Bar (Snow Fence) - 6000 Series, 2" high "T" extrusion with integral slot for color strip insertion.
 - 3. Color Strip – (optional and can be provided by installer or roof manufacturer) – 2" wide, 24 gage aluminum or steel painted with desired color.
- F. Fasteners (can be purchased from others) to be compatible with chosen roof application and meet specified pull out values as shown in load test data.





2.3 FINISH (choose one):

- A. Mill Finish – standard
- B. Powder Coated – available at additional cost

PART 3 – EXECUTION

3.1 EXAMINATION

- A. Substrate
 - 1. Inspect structure on which snow guard system is to be installed and verify that it will withstand any additional loading that it may incur. Notify general contractor of any deficiencies before installing Alpine SnowGuards.
 - 2. Verify that roofing material has been installed correctly prior to installing snow guards.

3.2 INSTALLATION

- A. Comply with architectural drawings and snow guard manufacturer's recommendations for location of system. Comply with manufacturer's written installation instructions for installation and layout.

Document Version 04.24.2015
07 72 53 Snow Guards

