

## SnowMax Bar Specification Sheet

### Snow Guards

#### PART 1 – GENERAL

##### 1.1 SUMMARY

###### A. WORK INCLUDES

1. SnowMax Bar attaches directly to the SnowMax-attachment brackets.
2. Coordinate with the installation of the roof to assure proper placement of the snow guards.
3. Provide appropriate snow guard and fasteners for the roof system

###### B. RELATED SECTIONS

1. Section 07600: Flashing and Sheet Metal. MasterFormat™ 2004 07 60 00
2. Section 07310: Shingles. MasterFormat™ 2004 07 31 00
3. Section 07320: Roofing Tiles. MasterFormat™ 2004 07 32 00
4. Section 07610: Metal Roofing. MasterFormat™ 2004 07 61 00
5. Section 07410: Metal Panels. MasterFormat™ 2004 07 41 00
6. Division 7: Thermal and Moisture Protection.

##### 1.2 SYSTEM DESCRIPTION

###### A. COMPONENTS:

1. SnowMax Bar Snow guard system consists of an aluminum bar
2. Coupling/Splice plate aluminum
3. Aluminum Ice Flag (IF) – optional and must be cut to match standing seam size

###### B. DESIGN REQUIREMENTS:

1. Spacing to be recommended by manufacturer or building engineer.
2. Install a minimum of 2 set screws per SnowMax attachment bracket with 1 fastener to attach bar to bracket.
3. Install a minimum of 1 tech screw to attach optional Ice Flag (IF)
4. It is important to design new structures or assess existing structures to make sure that they can withstand retained snow loads.



### 1.3 SUBMITTAL

- A. Submit manufacturer's specifications, standard detail drawings, installation instructions, and recommended layout.

### 1.4 QUALITY ASSURANCE

- A. Installer to be experienced in the installation of specified roofing material and snow guards for not less than 5 years in the area of the project.

### 1.5 DELIVERY / STORAGE / HANDLING

- A. Inspect material upon delivery and order replacements for any missing or defective items. Keep material dry, covered and off the ground until installed.

## **PART 2 – PRODUCTS**

### 2.1 MANUFACTURER

- A. Alpine SnowGuards. A division of Vermont Slate & Copper Services Inc.  
289 Harrel St. Morrisville, VT 05661, (888) 766-4273  
www.alpinesnowguards.com.

### 2.2 MATERIALS

- A. SnowMax Bar – 6000 Series Aluminum.
- B. SnowMax Coupling/Splice Plate – 6000 Series Aluminum
- C. Ice Flag (Optional) – 6000 series aluminum with (1) stainless steel tech screw

### 2.3 FINISH (choose one):

- A. Mill Finish – standard



## **PART 3 – EXECUTION**

### 3.1 EXAMINATION

#### A. Substrate

1. Inspect structure on which snow guard system is to be installed and verify that it will withstand any additional loading that it may incur. Notify general contractor of any deficiencies before installing Alpine SnowGuards.
2. Verify that roofing material has been installed correctly prior to installing snow guards.

### 3.2 INSTALLATION

- #### A. Comply with architectural drawings and snow guard manufacturer's recommendations for location of system. Comply with manufacturer's written installation instructions for installation and layout.

Document Version 12.07.2012  
07 72 53 Snow Guards

